


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 16 Twp. 24S Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines C SW SW

Lease Owner Rains & Williamson Oil Co.

Lease Name Burke Well No. 1

Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-26 1966

Application for plugging filed 5-26 1966

Application for plugging approved 5-26 1966

Plugging commenced 5-26 1966

Plugging completed 5-26 1966

Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ed Eads, Sublette, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4897' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	329'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 30 sacks of cement at 700'. Mud back to 380' and spot 35 sacks. Mud back to 45' and spotted 15 sacks.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 1 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Company
Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains, Partner (owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains, Partner
1425 Wichita Plaza Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of May, 19 66

My commission expires March 3, 1970

Mary J. Brown
Mary J. Brown Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.
 #1 Burke
 C SW SW Sec. 16-24S-21W
 Hodgeman County, Kansas

Contractor: Rains & Williamson Oil Co.
 Commenced: 5-14-66
 Completed: 5-26-66
 Remarks: Set 329° of 8-5/8" Surface
 Pipe with 225 sacks of
 cement.

FORMATIONS

Surface Soil & Clay	40°
Shale	331°
Shale & Shells	530°
Shale & Red Bud	940°
Sand	1045°
Shale & Red Bud	1459°
Anhydrite	1474°
Shale	1640°
Shale & Shells	2332°
Lime & Shale	2624°
Lime	2896°
Lime & Shale	3343°
Shale & Lime	3925°
Lime & Shale	4131°
Lime	4365°
Lime - Shale	4465°
Lime	4584°
Lime - Shale	4660°
Lime	4720°
Lime & Shale	4728°
Lime	4810°
Lime - Cherty	4870°
Lime	4897°
Rotary Total Depth (D & A)	4897°

RECEIVED
 STATE CORPORATION COMMISSION

JUN -1 1966

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of
 Kansas, County of Sedgwick, this 31st day of May, 1966.

My Commission Expires: 3-3-70

Mary J. Brown
 Mary J. Brown Notary Public