

15-083-20024-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 1 Twp. 24S Rge. (E) 23 (W)

Location as "NE/CNW%SW%" or footage from lines C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Mages "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 4, 1967
Application for plugging filed November 4, 1967
Application for plugging approved November 4, 1967
Plugging commenced November 4, 1967
Plugging completed November 4, 1967
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves

Producing formation Depth to top Bottom Total Depth of Well 4653' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	278'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 900'. Set plug. Cemented with 100 sacks cement. Heavy mud to 275'. Set plug. Cemented with 30 sacks cement. Heavy mud to 45'. Set plug. Cemented with 15 sacks to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
NOV 14 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn to, doth say: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 10th day of November, 1967

L. M. Whiting
L. M. Whiting Notary Public.

My commission expires May 10, 1970

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita, Kansas, 67202
 Rotary Drilling Commenced 10/23/67
 Rotary Drilling Completed 11/4/67

LOCATION: Mages "A" No. 1
 C SE NW Section 1-24S-23W
 Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (14 jts.) 8 5/8" surface casing set at 278' and cemented with 160 sacks cement. Circ. Complete at 10:45 PM, October 23, 1967. No oil string was run. D. & A., plugged November 4, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Clay & Lime Streaks	C. F. S.
842	Shale & Shells	4390'
865	Blaine	4425'
960	Red Beds	4440'
1115	Sand	4535'
1456	Shale & Shells	4540'
1490	Anhydrite	4600'
1720	Shale & Shells	4610'
2160	Shale & Lime Streaks	4625'
2290	Lime & Shale	4633'
2815	Lime	4643'
4005	Lime & Shale	4653'
4205	Lime	
4350	Lime & Shale	
4610	Lime	
4653	Mississippian, RTD	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 14 1967
 CONSERVATION DIVISION
 Wichita, Kansas

Slope Tests

3000'
3500'
4000'
4500'

S. L. M.

Board	4367.82'
Strap	4365.85'
Difference	1.97'

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
 C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 10th day of November, 1967, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
 L. M. Whiting
 Notary Public