


15-075-10011-0000

4p

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Hamilton County. Sec. 12 Twp. 26S Rge. 39 ~~38~~ (W)  
Location as "NE/CNW/SW" or footage from lines C-SE/4 of SW/4

Lease Owner Duncan Operating Co. - LaFortune Sr. Wilcox & Henry

Lease Name Klassen #1 Well No. \_\_\_\_\_

Office Address 740 Fourth Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-6-63 19\_\_

Application for plugging filed 1-6-63 19\_\_

Application for plugging approved 1-6-63 19\_\_

Plugging commenced 1-6-63 19\_\_

Plugging completed 1-6-63 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Liberal, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole was full and circulated w/drill pipe @ 3050 ft. A plug of 50 sxs of common cement was pumped through open end of drill pipe @3050.

A plug of 35 sxs of common cement was pumped through open end of drill pipe @ 1800 ft. A wooden plug was set at 40 ft. KBM and 10 sxs of cement was pumped in. Cement filled to bottom of cellar. 5 sxs of cement was used to plug rat hole and mouse hole as instructed by State Plugger, Mr. Scott.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 16 1963

1-16-1963

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Haliburton Cementing Company  
Address Elkart, Kansas

STATE OF Kansas COUNTY OF Sedgewick, ss.  
Thomas Elliott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas Elliott  
1210 Western Drive Liberal  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1963

My commission expires June 23, 1966  
Therese Neenan  
Notary Public.

WELL LOG

15-075-10011-0000

Well: Klassen #1  
 Location: Sec. 12-26S-39W  
 Hamilton County, Kansas  
 Owner: Wilcox & Henry

Spudding date: 12/9/62  
 Date casing set: 12/15/62  
 Date rotary completed: 1/5/63  
 Date cable completed: 1/6/63

FROM	TO	FORMATION	REMARKS
0	684	Surface Hole	
684	1090	Shale & Sand	
1090	1170	Shale	
1170	2000	Anhydrite & Shale	Ran 60 Jts. new 24# JS 55 Casing.
2000	2445	Shale & Lime	Total pipe ran less thrds. 1844.56.
2445	2535	Shale	Cemented w/Poz Mix & 200 sxs.
2535	3195	Shale & Lime	common w/2% C. C. Plug down @
3195	3283	Lime	7:00 p. m. Pumped plug to 1814.
3283	3675	Lime & Shale	Cemented w/560 Poz Mix w/4% Gel
3675	3725	Limed Chalk	200 common w/2% C. C. Pipe set
3725	3840	Lime & Shale	@1824 K. B. M.
3840	4150	Lime	
4150	4375	Lime & Chalk	
4375	4420	Lime	
4420	4540	Lime & Chalk	
4540	4596	Lime	
4596	4660	Lime & Shale	
4660	4752	Lime	
4752	4840	Shale & Lime	
4840	5066	Lime	
5066	5352	Shale & Lime	
5352	5440	Lime	
5440	5492	Lime & Chert	
5492	5600	Lime	
5600		T. D.	

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 24 1963  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Subscribed and sworn to before me this 11th  
 day of January, 19 63

I certify the above and foregoing to be a true and exact copy  
 of the original driller's log on the KLASSEN #1

*Johnnie Gene Jones*  
 Notary Public  
 My commission expires: 6/19/65

HERNDON, INC.  
~~HERNDON DRILLING COMPANY~~  
 By: *Seth Herndon Jr.*  
 Title: Seth Herndon, Jr. - President