

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kearney County. Sec. 14 Twp. 26S Rge. 35W (6) (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Panhandle Development Company

Lease Name Citizens Building & Loan Well No. 1-14

Office Address Box 1226, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed July 11, 1961 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced July 11, 1961 19

Plugging completed July 11, 1961 19

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5220 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

8 5/8" 842 circulated with cement.  
Filled hole with mud - spotted 120 sacks cement 2700' to 2300' -  
spotted 20 sacks cement at 800' - spotted 20 sacks cement at 400' -  
filled with mud to 40' - set plug and hulls - capped to base of cellar  
with 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1966  
3-4-1966

CONSERVATION COMMISSION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company Tools

Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Sedgewick, ss.

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack K. Wharton

Box 1226 Liberal Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1966

Deward S. Greville

My commission expires 11-5-67

Notary Public.

PANHANDLE DEVELOPMENT CO., INC.

P. O. BOX 1226



PH. MAIN 4-6981

15-093-10016-0000

LIBERAL, KANSAS

PANHANDLE DEVELOPMENT CO., INC.  
CITIZENS BUILDING & LOAN #1-14  
C NE NE, Sec. 14-26S-35W,  
Kearny County, Kansas

D R I L L E R ' S L O G

7-14-64

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1964

CONSERVATION DIVISION  
Wichita, Kansas

0 - 370	Sand
370 - 855	Sand & Clay
855 - 1000	Clay & Red Beds
1000 - 1740	Red Bed, Sand & Anhydrite
1740 - 2070	Sand & Shale
2070 - 2390	Red Bed & Shale
2390 - 2725	Lime & Shale
2725 - 2860	Shale and Lime
2860 - 4170	Lime and shale
4170 - 5220	Lime with thin shale beds
5220	R.T.D. D & A

Set 8 5/8" casing @ 842.14' Ground level with 250 sacks lite weight cement, 2% C.C. and 200 sacks common cement with 2% C.C.

STATE OF KANSAS )  
  ) ss.  
COUNTY OF SEWARD )

I, Jack K. Wharton, do hereby certify that the above and fore-going is a true and correct copy of the driller's log of the above mentioned well as reflected by the files of Panhandle Development Co., Inc.

\_\_\_\_\_  
Jack K. Wharton

Subscribed and sworn to before me, a Notary Public, in and for the above said county and state.

\_\_\_\_\_  
Laressa Guild

My Commission expires September 16, 1964.