

To: 1 040700  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,341- 000018 R  
S/2 NE NE, SEC. 8, T. 24 S, R. 16 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name & Address P.O. Box 8647  
Wichita, KS 67208

4290 feet from S section line  
660 feet from E section line  
Lease Name Smith "A" Well # 1  
County Edwards 139.75  
Well Total Depth 4300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 10 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4299' w/100 sx cement, PBD 4295', Perfs at 4238-58'

1st plug sand back to 4190' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 6 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 4 sx cement on top of sand  
bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 650 psi and shut in 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
10-9-92  
OCT 9 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2322' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOLVED

I (old ~~XXXXXX~~) observe this plugging.

DATE 10-29-92

INV. NO. 36637

Signed Stephen J. Puffer  
(TECHNICIAN)