

9-15-047-00099-0901  
20

To: 1 031029  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202.

API NUMBER 15-Drill Completion 9/28/76 OWWO

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company  
Name & Address P.O. Box 780167  
Wichita, KS 67207

SE SW SW, SEC. 18, T 24 S, R 16 W/R

330 feet from S section line  
4290 feet from E section line

Lease Name Campbell "B" Well # 1-18

County Edwards 143.20

Well Total Depth 4406 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 feet 207

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 20 Month: 9 Year: 19 89

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4371' PBT 4311' Perfs at 4266-70' Elevation 2093' KB

1st plug pump 1 or 2 sx hulls and 25 sx cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

9-22-89  
RECEIVED  
STATE CORPORATION COMMISSION

SEP 22 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing. Wichita, Kansas  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I should observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 9-28-89

INV. NO. 25973  
9-20