

To: 1 041192
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-047-20,782-0000

NW NW NW, SEC. 18, T. 24 S, R. 16 W/E

440 feet from NX section line

440 feet from WE section line

Lease Name Campbell # Well B 2-18

County Edwards

Well Total Depth 4417 143.55 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Co., L.L.C.

Name: _____
Address P.O. Box 780167

Wichita, KS 67278-0167

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:15 a.m. Day: 30 Month: 7 Year: 19 96

Plugging proposal received from Thom Pool

(company name) F.G. Holl Co. (phone) 316-995-3171

work: 4 1/2" at 4412' w/225 sx cement, PBTD 4354', Perfs at 4323-27'

1st plug sand back to 4275' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 30 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 175 psi.

RECEIVED
KANSAS CORPORATION COMMISSION
8-2-96
AUG 02 1996

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2380' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Steve Pfeifer
(TECHNICIAN)

INVOICED
DATE AUG 07 1996
INV. NO. 46192