

To: 1 030558
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,212 - 0000

NE NE NE , SEC. 10 , T 24 S, R 17 W/EX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Leon Smith Well # 4-10

Operator: F. G. Holl
Name & Address 6427 East Kellogg
Wichita, KS 67207

County Edwards
Well Total Depth 4495 146.09 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 pm Day: 28 Month: October Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4489' Perfs at 4326-4336'

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 28 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dump 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi

Remarks: Recovered 3017' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 11-1-85
INV. NO. 10863

RECEIVED
STATE CORPORATION COMMISSION
Signed Steve Shumant (TECHNICIAN)
NOV 1 1985