

302 R

MAR 29 1989

API NUMBER 15-047-20,639-0000

To: 1 120238  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App. NW NW SW, SEC. 10, T 24 S, R 17 W Ex  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2240 feet from S section line  
4880 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Boyd Well # 2-10

Operator: F.G. Holl Company  
Name &

County Edwards 144.79

Address P.O. Box 780167  
Wichita, KS 67207

Well Total Depth 4455 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 29 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4453' PBTD 4416' Perfs at 4327-4380' (2 sets)

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 1 p.m. Day: 29 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4270' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement

Pumping pressure 0-500 psi and shut in 150 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
4-3-89  
APR - 3 1989

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2310' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form)

INVOICED (10/10/88) observe this plugging.

Signed *Quanshankin*  
(TECHNICIAN)

DATE 4-19-89

INV. NO. 24341