

11-21

To: 1-120346
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,330-0000
SW SW NW SEC. 10, T 24 S, R 17 W/EX

3030 feet from S section line
4890 feet from E section line

Lease Name L. Smith Well # 1-10
County Edwards 144.30

Well Total Depth 4440 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 240

TECHNICIAN'S PLUGGING REPORT
Operator License # 5056
Operator: F.G. Holl Company
Name & Address 6427 East Kellogg
P.O. Box 780167
Wichita, KS 67207

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 21 Month: 11 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4439' PBT 4394' Perfs at 4331-34'

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 21 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4280' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

11-29-89
NOV 29 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 12-7-89

Signed Deane Banks
(TECHNICIAN)

INV. NO. 26682