

1 120485

10-10 15-047-30062-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 4/7/78
C. NE SE, SEC. 14, T 24 S, R 17 W/EX

1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Fertig Well # 1

Operator: F.G. Holl Company

County Edwards 145.27

Name & Address

P.O. Box 780167

Well Total Depth 4470 feet

Wichita, KS 67278

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4469' w/175 sx cement, PBTD 4454', Perfs at 4330-34'

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 10 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4280' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 150 lbs. hulls and 125 sx cement.

Pumping pressure 0-450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION

OCT 17 1990

Signed *Steve Durrant* (TECHNICIAN)

DATE OCT 23 1990

INV. NO. 29697

CONSERVATION DIVISION
Wichita, Kansas