

1 090250

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,224-0000

NE NW SE, SEC. 14, T 24 S, R 17 W/X
2310 feet from N SE Corner of
1650 feet from W SE Corner of
XXX section line
XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Fertig Well # 3-14

Operator: F. G. Holl
Name & Address 6427 East Kellogg
Wichita, KS 67207

County Edwards 145.60
Well Total Depth 4480 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Co. License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: noon Day: 17 Month: November Year: 19 84

Plugging proposal received from Tom Myers

(company name) Sterling (phone) 316-268-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1080' with 50 sx cement

2nd plug at 540' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by R. B. Bartlett
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 pm Day: 17 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1080' with 50 sx cement, 2nd plug at 540' with 70 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

11-21-84 NOV 21 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.) Wichita, Kansas

I (did / did not) observe this plugging.

Signed R. B. Bartlett S.D.
(TECHNICIAN)

DATE 12-3-84

INV. NO. 5745