

1 051033

4-6-88

API NUMBER 15-047-20,369-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE, SE SW, SEC. 14, T 24 S, R 17 W/EX

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Chalk Well # 1-14

Operator: F.G. Holl Company

County Edwards 146.38

Name & Address P.O. Box 780167

Well Total Depth 4504 feet

Wichita, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 6 Month: 4 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4508' PBD 4479' Perfs at 4353-57', 4321-25'

1st plug sand back to 4275' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:10 p.m. Day: 6 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2211' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
4-11-88  
APR 11 1988

INVOICED  
observe this plugging.

DATE 4-12-88

Signed Richard W. Gray  
(TECHNICIAN)

INV. NO. 20346