

To: 1 041193
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-21,130-0000
NE NE SW, SEC. 14, T 24 S, R 17 W/E
2310 feet from S section line
2970 feet from E section line

7-30

TECHNICIAN'S PLUGGING REPORT

Operator License / 5056

Lease Name Chalk Well # 2-14

Operator: F.G. Holl Co., L.L.C.

County Edwards

Name:
Address P.O. Box 780167

Well Total Depth 4490 145.92 feet

Wichita, KS 67278-0167

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12 p.m. Day: 30 Month: 7 Year: 19 96

Plugging proposal received from Thom Pool

(company name) F.G. Holl (phone) 316-995-3171

Work: 4 1/2" at 4484' w/225 sx cement, PBSD 4461', Perfs at 4324-26, 4330-34'

1st plug sand back to 4275' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 30 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement

Maximum pressure 500 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
9-2-96
AUG 07 1996

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2198' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 07 1996

INV. NO. 46193

observe this plugging.

Signed: *Steve Pfeifer*
(TECHNICIAN)