

To: 1 031437  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-047-21,205-0001  
NW SW NW, SEC. 14, T. 24 S, R. 17 W/E  
3630 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056  
Operator: F.G. Holl Company, LLC  
Name & Address: P.O. Box 780167  
Wichita, KS 67278-0167

Lease Name Miller B Well # 2-14  
County Edwards 144.49  
Well Total Depth 4446 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1 p.m. Day: 20 Month: 1 Year: 1997

Plugging proposal received from Thom Pool  
(company name) F.G. Holl Co. (phone) 316-995-3171

logs: 4 1/2" at 4440' w/225 sx cement, PBTD 4410', Perfs at 4314-4418, 4364-68'  
1st plug pump 50 sx cement on bottom, Plug through 4 1/2" casing:  
2nd plug at 2050' with 50 sx cement, 3rd plug at 1200' with 50 sx cement,  
4th plug at 600' with 50 sx cement, 5th plug at 210' with 40 sx cement,  
6th plug pump 10 sx cement at 40-0'.  
7-22-97

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None   
Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 1 Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement on bottom, Pumped through 4 1/2" casing:  
2nd plug at 2050' with 50 sx cement,  
3rd plug at 1200' with 50 sx cement,  
4th plug at 600' with 50 sx cement,  
5th plug at 210' with 40 sx cement, 6th plug at 40-0' with 10 sx cement. Heavy mud between plugs.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2210' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I (XXXXXX) did not observe this plugging.

DATE JAN 23 1997

Signed Steve Durrant (TECHNICIAN)

INV. NO. 47425  
1-20