

To: 1 120483
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67278

10-10
API NUMBER 15-047-21,120-0000

SE SE SEC. 14, T 24 S, R 17 W/XX

330 feet from S section line

330 feet from E section line

Lease Name Fertig Well # 2

County Edwards 145.92

Well Total Depth 4490 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4477' w/225 sx cement, PBSD 4455', Perfs at 4340-44, 4355-59, 4370-74'

1st plug sand back to 4290' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 10 Month: 10 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing to 4290' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-350 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 23 1990

INV. NO. 29698

RECEIVED

10-17-90
OCT 17 1990

Signed Steve Durrant
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84