

1 030973

8-27-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,325 - 0000
C NW NW, SEC. 20, T 24 S, R 16 WEX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

4620 feet from S section line
4620 feet from E section line

Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Brasfield Well # 2-20
County Edwards 144.07

Well Total Depth 4433 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, Sterling KS 67579

Company to plug at: Hour: 4 a.m. Day: 27 Month: 8 Year: 19 88

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1106-26'
Elevation 2088'

1st plug at 1130' with 50 sx cement, 2nd plug at 560' with 90 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 a.m. Day: 27 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1130' with 50 sx cement,

2nd plug at 560' with 90 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 8-31-88

Signed Steve Hume (TECHNICIAN)

INV. NO. 22058

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1988
CONSERVATION DIVISION
Wichita, Kansas
8-30-88

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... August 19 1988 month year

API Number 15-047-21,325-0000

OPERATOR: License # 5056 Name F. G. Hall Company Address P. O. Box 780167 City/State/Zip Wichita, Kansas 67278-0167 Contact Person Elwyn H. Nagel Phone (316) 684-8481

Sec 20 Twp 24 S Rg 16 West 4620 Ft. from South Line of Section 4620 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5142 Name Sterling Drilling Company City/State Sterling, Kansas 67579

Nearest lease or unit boundary line 660 feet County Edwards Lease Name Brasfield Well # 2-20 Ground surface elevation 2088 est. feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: X yes no Depth to bottom of fresh water 150 feet Depth to bottom of usable water 280 feet Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 300 Conductor pipe required NA Projected Total Depth 4475 feet Formation Viola

Well Drilled For: X Oil Storage X Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Aug. 11, 1988 Signature of Operator or Agent W. Bryce Bidleman Title Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt. 1 X This Authorization Expires 8-11-89 Approved By LKM 8-11-88

EFFECTIVE DATE: 8-16-88

Spud 8-19-88

300 of 8 3/8"

art well Yes.

Sec 20 Twp 24 S Rg 16 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 1140 or formation with 50 sx feet of cement 2nd plug @ ft. deep 570 or formation with 50 sx feet of cement 3rd plug @ ft. deep 300 or formation with 50 sx feet of cement 4th plug @ ft. deep 40 or formation with 10 sx feet of cement & 1/2 sx hulls & 5th plug @ ft. deep or formation with feet of Halliburton plug (2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Van... TD 4433 FORMATION Viola SURFACE PIPE 8 3/8 @ 307 ANHYDRITE 1106 ELEVATION 2088 STARTING TIME & DATE 4:00 AM 8-21-88 COMPLETION TIME & DATE 5:30 1st PLUG @ 1130 FT. W/ 50 SX 2nd PLUG @ 560 FT. W/ 90 SX 3rd PLUG @ FT. W/ SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ ch 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Halliburton TECHNICIAN 60/4069 Jell

RECEIVED CONSERVATION DIVISION Wichita, Kansas AUG 30 1988 8-30-88