

11-20

To: 1 120345
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,795- 0000
SE SE SE, SEC. 23, T 24 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 30149

330 feet from S section line
330 feet from E section line
Lease Name Bernard A. Meyer Well # 4

Operator: BTA Operating
Name & Address: Box 3846
Edmond, OK 73083

County Edwards 135.85
Well Total Depth 4133 4180' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 20 Month: 11 Year: 19 89

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4179' PBTD 4133' Perfs at 3797-3813' Elevation 2059' GL
1st plug sand back to 3740' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 400 lbs. hulls, 20 sx gel, and 175 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3740' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-500 psi and shut in 200 psi.

NOV 29 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing. 11-29-89
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-89
INV. NO. 26665

Signed *Dean Rankin*
(TECHNICIAN)