

3-24-88

1 061081

API NUMBER 15-047-20,763-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NW, SEC. 23, T 24 S, R 16 W/4X
2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Embry "A" Well # 1-23

Operator: F.G. Holl Company
Name & Address: 6427 East Kellogg
Wichita, KS 67207

County Edwards 141.54
Well Total Depth 4355 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 263'

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 4:30 p.m. Day: 24 Month: 3 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4351' PBD 4040' Perfs at 3810-14'

1st plug sand back to 3760' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 24 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3760' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement,

gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

RECEIVED 10 sx
STATE CORPORATION COMMISSION
3-28-88
MAR 28 1988

Maximum pressure 450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 3-29-88

INV. NO. 20239