

1 030619

15-047-30061-0001

Comp. 1-7-55 OWWO 7-12-79

OWWO Comp. 1979

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

C SW SE , SEC. 30 , T 24 S, R 16 W X

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name 1. Breitenbach Well # "A" 1-30

Operator: F. G. Holl

County Edwards

Name &

Address 6427 East Kellogg

Well Total Depth 4485' <sup>143.76</sup> feet

Wichita, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:00 pm Day: 17 Month: December Year: 19 85

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4459' PBD 4400' Perfs at 4410-16'; 4341-45'

1st plug pump 1 sack hulls and 30 sx cement to bottom and push plug to 4000'

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 pm Day: 17 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx cement to bottom and pushed

plug to 4000', 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx

gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 500 psi and shut in 200 psi

Remarks: Recovered 2500' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

STATE CORPORATION COMMISSION

Signed

Steve Duntz  
(TECHNICIAN)

DATE DEC 27 1985

INV. NO. 11742

CONSERVATION DIVISION

FORM CP-2/3  
Rev. 01-84