

1 031353

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

9-25

API NUMBER 15-047-20,553-0000

NE NE NW, SEC. 35, T 24 S, R 16 W/EK

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Producers, Inc. of Kansas

Name: P.O. Box 8647

Address: Wichita, KS 67208

Lease Name Turner Well # 1

County Edwards 142.19

Well Total Depth 4375 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:30 p.m. Day: 25 Month: 9 Year: 19 95

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

logs: 4 1/2" at 4374' w/100 sx cement, PBTD 4363', Perfs at 4304-14, 4290-4300'

1st plug sand back to 50' above perfs and dump 4 sx cement on top,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 25 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement; 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

9-28-95

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2500 of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

DATE 10-9-95

INV. NO. 43709

RECEIVED STATE CORPORATION COMMISSION

SEP 28 1995

CONSERVATION DIVISION Wichita, Kansas

Steve Mervant (TECHNICIAN)