

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20346-00-00
Spot: CS2NENE Sec/Twnshp/Rge: 33-24S-16W
4290 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: FISHER Well Number: 1
County: EDWARDS Total Vertical Depth: 4390 feet
Operator License No.: 8061 Conductor Pipe: Size feet: 3 1/2" 68
Op Name: OIL PRODUCERS, INC. OF KANSAS Surface Casing: Size 8.625 feet: 301 WITH 250 SX CMT
Address: PO BOX 8647 Production: Size 4.5 feet: 4387 WITH 125 SX CMT
WICHITA, KS 67208 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/19/2002 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTIRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: PLUG AT 1060' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 320' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/19/2002 11:20 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 4384'. PERFS AT 4294-4333'. SANDED TO 4226' & 4 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 2000' WITH 10 SX GEL TO KILL OIL FLOW. 2ND PLUG AT 1060' WITH 10 SX GEL - 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

RECEIVED
NOV 27 2002 11-27-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2210' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard M. Lacey

(TECHNICIAN)

INVOICED

DATE 12-2-02

INV. NO. 2003060880