

1 030775

15-04730005-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

C SE SE, SEC. 22, T 24 S, R 17 W/E

660 feet from S section line

660 feet from E section line

Lease Name Mary Helen Crosswell # 1-22

County Edwards 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 232

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Operator: Sterling Drilling Company
Name & Address P.O. Box 129
Sterling, KS 67579

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 13 Month: 1 Year: 19 87

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4545' PBD 4370' Perfs at 4343-46' Elevation 2112' KB

1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3' sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 p.m. Day: 13 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 4 sx cement on top of sand

through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx

cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Recovered 2400' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED Reserve this plugging.

DATE 1-16-87

Signed Steve Duntz (TECHNICIAN)

INV. NO. 18930

1-13