

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21276-00-00
Spot: CE2E2NE Sec/Twnshp/Rge: 2-24S-17W
3960 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: TWITCHELL Well Number: 3-2
County: EDWARDS Total Vertical Depth: 4445 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet: 3 1/4 46
Surface Casing: Size 8.625 feet: 296 WITH 200 SX CMT
Production: Size 4.5 feet: 4350 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/14/2002 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON PHLOGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND BACK TO 4240' & 4 SX CMT ON TOP. 1ST PLUG AT 1130' WITH 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/14/2002 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4350'. PERFS AT 4290-4302'. SANDED TO 4240' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1130' WITH 13 SX GEL - 50 SX CMT - 2 SX GEL. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

4-1-2002
RECEIVED
APR 01 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 1600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 4-2-02
INV. NO. 2002061598

MAR 19 2002


Form CR-273