

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21407-00-00
Spot: NWNENE Sec/Twnshp/Rge: 2-24S-17W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: TWITCHELL Well Number: 4-2
County: EDWARDS Total Vertical Depth: 4435 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet: 3/44.14
Surface Casing: Size 8.625 feet: 275 WITH 225 SX CMT
Production: Size 4.5 feet: 4434 WITH 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/15/2002 2:15 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: SAND BACK TO 4200' & 4 SX CMT ON TOP. 1ST PLUG AT 1120' WITH 50 SX CMT. 2ND PLUG AT 305' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/15/2002 3:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PERFS AT 4286-96, 4255-59'. SAND BACK TO 4205' & 4 SX CMT ON TOP WITH BAILER. 1ST PLUG SPOT 13 SX GEL & 50 SX CMT AT 1127'. 2ND PLUG SPOT 50 SX CMT AT 300'. 3RD PLUG SPOT 10 SX CMT AT 0-40'. GOOD CIRCULATION.

RECEIVED
MAR 22 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT. RECOVERED 1800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

INVOICED MAR 18 2002

DATE 5-01-02

INV. NO. 2002061726