

To: 1 031240
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-10 API NUMBER 15- 047-20,988-0000
N/2 N/2 NW, SEC. 2, T 24 S, R 17 W/X

4950 feet from S section line
3960 feet from E section line
Lease Name Massey "C" Well # 1-2
County Edwards
Well Total Depth 4420 143.65 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

TECHNICIAN'S PLUGGING REPORT
Operator License # 5056
Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67278-0167

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 10 a.m. Day: 10 Month: 8 Year: 19 93

Plugging proposal received from Judy
(company name) Pratt Well Service, Inc. (phone) 316-672-5901

work: 4 1/2" at 4414' w/225 sx cement, PBTD 4396', Perfs at 4362-66', Plug at 4330', 4263-68'
1st plug set bridge plug at 4080' with 4 sx cement on top,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:45 a.m. Day: 10 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set bridge plug at 4080' with 4 sx cement on top,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.
Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing.

RECEIVED STATE CORPORATION COMMISSION

AUG 19 1993 8-13-93

INVOICED

DATE AUG 18 1993

WV. NO. 38376

Signed Steve Durmont (TECHNICIAN)