

To: 1030559  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,682 - 0000  
NE NE NE, SEC. 2, T 24 S, R 17 (W/E)  
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Twitchell Well # 1-2

Operator: F. G. Holl  
Name  
Address 6427 East Kellogg  
Wichita, KS 67207

County Edwards  
Well Total Depth 4360 141.70 feet  
Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 28 Month: October Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4359' PRTD 4325' Perfs 4245 1/2 - 4249 1/2'

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

hulls, release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 pm Day: 28 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,  
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pump 150 sx cement.

Maximum pressure 300 psi and shut in 50 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

Signed Steve Luthi  
(TECHNICIAN)

DATE 11-1-85

NOV 1 1985 11-1-85

INV. NO. 10862

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84