

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21015-00-00
Spot: NESENWNW Sec/Twnshp/Rge: 31-32S-31W
4422 feet from S Section Line, 4006 feet from E Section Line
Lease Name: ELLIOTT Well #: 1-31
County: SEWARD Total Vertical Depth: 6002 feet

Operator License No.: 34089
Op Name: AGRICULTURAL ENERGY SERVICES
Address: PO BOX 31865
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	6002	1635	WITH 165 SX CMT
SURF	8.625	1600		WITH 600 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2015 9:00 AM
Plug Co. License No.: 31985 Plug Co. Name: GONZALES WELL SERVICE, INC
Proposal Rcvd. from: MIKE BRADY Company: BRADY PUMPING SERVICES Phone: (620) 629-5660

Proposed Plugging Method: CMT RETAINER AT 2600' WITH 30 SX CMT BELOW & 5 SX CMT ON TOP OF RETAINER. PLUG AT 1640' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 11/24/2015 5:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CMT RETAINER AT 2605' WITH 30 SX CMT BELOW & 5 SX CMT ON TOP OF RETAINER. 1ST PLUG AT 1638' WITH 50 SX CMT. 2ND PLUG AT 567' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5580	5584		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature]

5A

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

RECEIVED
DEC - 3 2015
KCC DODGE CITY [Signature]

DEC 09 2015
CONSERVATION DIVISION
WICHITA, KS

12-9-2015

Form CP-2/3

12/18/15
ckm