

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155 20,814

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name E.S.T. Oil & Gas Exploration, Inc.

Complete Address Box 28, Inman, Kansas

Lease Name Bartel Well No. 1

Location SE SW Sec. 36 Twp. 22 Rge. 4 (~~East~~ West)

County Reno Total Depth 3675'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling and Halliburton Co.

Address Box 373, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour: 2:30 PM Day: 11 Month: March Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

PBTD-3292 5 1/2" - 3643' - 150 sacks PerF 3284-44'
Hole Filled with sand to 3200' and cemented with 5 sacks
Cement. Casing parted and Fished recovering 1478' - also shot
a 2500' before pulling in two. Hole squeezed with 25 sacks gel-mud,
7 sacks hulls and 150 sacks 50/50 foamix with 4% gel and 38 c.c.
pumped into 10 3/4" surface casing. Cement went down to 62' and
then filled to surface.

Amount of Surface Casing: 10 3/4" - 255 - circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICE

DATE 3-24-82

INV. NO. 9730-W

3-17-82