



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

JAN 14 1963
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Jan. 9, 1963.

JAN 14 1963
 1-14-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bill Draper of Prime Drilling Co. has this

date requested permission to plug the following described well:

Mr. Bill Draper guarantees payment of the plugging fee.

Operator's full Name: C. H. Spoor Jr.

Complete Address: 1078 Armour Lane Wichita, Kansas.

Lease Name: Wilcox #1 Well No. #1

Location: C-NE-NW Sec. 10 Twp. 24S Rge. 17 (E) (W) X

County Edwards County Total Depth 4418 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bill Draper was instructed to plug the well as follows:

244' of 8 5/8" surface pipe circulated with cement. Hole
filled with mud to 240', 1/2 sack hulls, 1st cementing plug
and 20 sacks cement. Hole filled to 40' with mud, 1/2 sack
hulls, 2nd cementing plug and 10 sacks cement to base of
cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

Herbert J. Gustus
 Conservation Division Agent