

15-155-01649-0000

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 29, 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompson of Forbes Casing Pulling Inc. has this  
date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Thomas A. Allan

Complete Address: R. R. #1, Great Bend, Kansas

Lease Name: Cantwell Well No. 1

Location: C SE SE Sec. 18 Twp. 22 Rge. 8 (E) (W) X

County Reno Total Depth 3600' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Thompson was instructed to plug the well as follows:

Push 4 1/2" plug to 3580'. Fill hole with sand to 3570' and cement with  
3 sacks. Fill hole with mud to 220'. Set rock bridge from 220' to  
210' and cement hole with 20 sacks. Fill hole with mud to 40'. Set  
rock bridge from 40' to 30' and cap hole with 10 sacks cement.

FILED  
CORPORATION COMMISSION

1-10-67  
JAN 10 1967

CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

[Signature]  
Conservation Division Agent