



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg.  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 7 - 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

2-7-68

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

January 22, 1968

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Thomas H. Allan

Complete Address: R. R. # 1, Great Bend, Kansas 67530

Lease Name: Cantrell Well No. 2

Location: C NE SE Sec. 19 Twp. 22 Rge. 8 (E) (W) X


County: Reno Total Depth 3586' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

- Fill hole with sand to 3500' and cement with 5 sacks.
- Fill hole with mud to 225'. Set rock bridge from 225' to 215' and
- cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge
- from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent