



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

July 12, 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Schmucker "D" Well No. 1

Location: ~~NW NW SE~~ CNWSE Sec. 19 Twp. 22 Rge. 8 (B) (W) X

County Reno Total Depth 3608' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

Circulate Heavy mud. Fill hole with mud to 205'. Push  
plug and 1/4 sack hulls to 205' and cement with 20 sacks  
through drill pipe. Fill hole with mud to 40'. Push  
plug and 1/4 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

RECEIVED  
 STATE CORPORATION COMMISSION  
 7-19-63  
 JUL 19 1963

Very truly yours,

*Arthur J. Brown*  
 Conservation Division Agent

CONSERVATION DIVISION  
 Wichita, Kansas