

State of Kansas



15-155-01651-0000  
FORM - CP-2  
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

October 25, 1965

RECEIVED  
STATE CORPORATION COMMISSION  
11-9-65

NOV 9 1965

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling Inches this  
date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Barber Well No. 1

Location: C NW NE Sec. 20 Twp. 22 Rge. 8 ~~SEX~~ (W) X

County Reno Total Depth 3605' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pully was instructed to plug the well as follows:

Push 4 1/2" plug to 3540'. Fill hole with sand to 3530' and  
cement with 3 sacks. Fill hole with mud to 210'. Set rock  
bridge from 210' to 200' and cement hole with 20 sacks.  
Fill hole with mud to 40'. Set rock bridge from 40' to 30'  
and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent