

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. WICHITA, KANSAS 67202

RECEIVED
CONSERVATION COMMISSION

AUG 16 1966
8-16-66

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 8, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Grover Well No. 2

Location: C NW NW Sec. 20 Twp. 22 Rge. 8 (E) (W) X

County Reno Total Depth 3610' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

Fill hole with sand to 3580' and cement with 4 sacks.

Fill hole with mud to 235'. Set rock bridge from 235' to 225' and
cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge
from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent