

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

July 12, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1978
7-25-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this

date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.Operator's full Name: Barnett Oil, Inc.Complete Address: 1625 Vickers-KSB&T Bldg., Wichita, Kansas 67202Lease Name: Drake Well No. 1Location: C NE SW Sec. 5 Twp. 22 Rge. 9 (E) (W) XCounty: Reno Total Depth 3655' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Rice was instructed to plug the well as follows:Fill hole with mud. Pump 40 sacks cement through drill pipeat 500'. Pump 25 sacks cement through drill pipe at 210'.Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sackscement. Bridge rathole and cement with 2 sacks cement.8-5/8" surface casing set at 222'--cement circulated.

Very truly yours,

Arthur D. Loman
Conservation Division Agent