

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 4, 1962.

DEC 7 1962
 12-7-62
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Frank Neff of Nadel & Gussman has this date requested permission to plug the following described well:

Mr. Frank Neff guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman

Complete Address: 1714 1st Nat'l. Bldg., Tulsa, Okla.

Lease Name: Shriver Well No. #1

Location: SW-SE-SE Sec. 14 Twp. 29 Rge. 14 (E) (W) X

County Pratt Total Depth 4548' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Frank Neff. was instructed to plug the well as follows:

780' of 8 5/8" surface pipe circulated with cement. Hole filled to 775' with heavy drill mud, 1 sack hulls, 1st cementing plug and 25 sacks cement. Hole filled to 40' with heavy drill mud, 1 sack hulls, 2nd cementing plug & 15 sacks cement to base of cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

Herman Gustus
 Conservation Division Agent