

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County. Sec. 8 Twp. 22S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner John C. Graves

Lease Name Culbertson Well No. 1

Office Address Box 332, El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 27, 19 63

Application for plugging filed May 27, 19 63

Application for plugging approved May 27, 19 63


Plugging commenced May 27, 19 63

Plugging completed May 27, 19 63

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3537 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 210 feet. Followed by wooden plug and 1/4 sack hulls. Placed 20 sacks cement onto hulls. Mudded up with heavy mud to 35 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1963
6-11-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address Box 332, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
JOHN C. GRAVES (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John C. Graves*
Box 332, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 63

My commission expires April 30, 1967 Betty Brandt Notary Public.



R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves
Box 332
El Dorado, Kansas

DRILLING COMMENCED: May 21, 1963

CONTRACTOR: Graves Drilling Co , Inc.
Box 332
El Dorado, Kansas

DRILLING COMPLETED: May 27, 1963

CASING RECORD: 5 Jts. - 215' - 8-5/8" new
surface with 200 sx. cement

LOCATION: Culbertson No. 1
C SE NW
Section 8-22S-8W
Reno County, Kansas

0 - 100	Sand & shale
100 - 150	Sand
150 - 213	Shale
213 - 775	Lime & shale
775 - 1425	Shale
1425 - 1585	Shale & lime
1585 - 1655	Lime
1655 - 2090	Lime & shale
2090 - 2385	Shale & lime
2385 - 2660	Lime & Shale
2660 - 2870	Shale & lime
2870 - 3000	Lime
3000 - 3197	Lime & shale
3197 - 3537	Lime
3537	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1963

6-11-63
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
President

STATE OF KANSAS)
BUTLER COUNTY) SS

Subscribed and sworn to before me, a Notary Public, this 28th day of May, 1963.

My commission expires:
April 30, 1967

Betty Brandt
Notary Public