

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Schack #1

WELL NUMBER _____

SPOT LOCATION 660' FSL 660' FE

SEC. 15 TWP. 24 RGE. 16 (R) or (C)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 5/9/84

Plugging Completed 5/14/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sun Exploration & Production Co.

ADDRESS Box 35567, Tulsa, Ok. 74135

PHONE # (918) 496-2500 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ if not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4301'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	380'	none
				5 1/2"	4301'	1995'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged bottom with 10 sacks common cement to 4200'. Plug went to bottom. Replugged bottom with 75 sacks cement to 3364'. Shot pipe at 2800', 2500', 2200' & 1995'. Pulled 32 joints. Filled hole with gel, pumped 50 sacks of cement in hole at 1007', pulled casing out to 443', loaded with gel again, ran 40 sacks cement, pulled rest of casing out of hole (63 joints total). loaded hole with gel & filled to top with cement. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address -Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1984



My Commission expires:

[Signature]
Notary Public