


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Range 16 County Sec. 16 Twp. 22 Rge. 8 (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Mull Drilling Company, Inc.
Lease Name Henry Well No. 5
Office Address 1625 Wichita Plaza Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 6-9-67 19
Application for plugging approved 6-10-67 19
Plugging commenced 6-19-67 19
Plugging completed 6-22-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	229	None
				4 1/2	None	3156

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
JUN 26 1967

Moved in. Rigged up. Sanded to 3550'. Dumped 3 sacks of cement.
Cleaned out cellar. Working pipe,
Working pipe. Shot pipe at 3150',
Working pipe. Pulling pipe.

Pulling pipe. Railed hole down. Set rock bridge at 225'. Dumped 20 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of June, 19 67

My commission expires May 27, 1969

Notary Public.

WELL LOG

15-155-02423-0000

COMPANY Mull Drilling Co.

SEC. 16 T-22S R. 8W

FARM Henry

NO. ~~15~~ #5

LOC. C SW SW


TOTAL DEPTH 3565'

COUNTY Reno

COMM. 7-14-63

COMP. 7-22-63

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 223' w/205 SX
4 1/2" @ 3560' w/75 SX

ELEVATION 1692' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 110' Shale and Shells
- 140' Sand
- 234' Red Bed
- 270' Red Bed and Shale
- 280' Post Rock
- 560' Shale and Red Bed
- 1210' Shale and Shells
- 1485' Shale, Shells, and Lime
- 1860' Lime
- 2070' Shale and Lime
- 2435' Shale and Lime Streaks
- 2810' Shale and Lime
- 2970' Lime
- 3020' Shale
- 3034' Lime
- 3128' Shale and Lime
- 3458' Lime
- 3531' Lime and Shale
- 3565' Lime
- 3565' RTD

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1967
6-12-67
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company
upon oath state the above and foregoing is a true and correct copy of the log of the Henry B-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 26th day of July 19 63

My Commission Expires: October 24th, 1966

Brankley
NOTARY PUBLIC