

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,341-0000

LEASE NAME Smith

WELL NUMBER A#1

         Ft. from S Section LI

         Ft. from E Section LI

SEC. 8 TWP. 24 RGE. 16 (W)

COUNTY Edwards

Date Well Completed 7-89

Plugging Commenced 10-6-92

Plugging Completed 10:30 AM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oil Producers, Inc.

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE# (316) 672-6373 OPERATORS LICENSE NO. 8061

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-6-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filled? yes If not, is well log attached?         

Producing Formation Miss Depth to Top 4238 Bottom 4258 T.D. 4300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	311	0
				4 1/2	4299	2322

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from          feet to          feet each  
Bottom plug: Sanded to 4190 & bailed 4 sx cement.

Top plug: Pumped down 8 5/8: 300 lbs hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb hulls,  
Wiper plug, 150 sx 60/40 with 6% gel. Had maximum pressure of 650 lbs & shut in of 100 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License # 635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God:

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 6 day of October, 19 92



Anna K. Burke  
Notary Public

My Commission Expires: 4-30-96