


15-047-50015-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Flat

Edwards County, Sec. 9 Twp. 24 Rge. 16 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Messman - Ringhart Oil Co.
Lease Name Enlow Well No. #2
Office Address 1432 Wichita Plaza ; Wichita, Kans. 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed March 1973
Application for plugging approved March 1973
Plugging commenced March 26 1973
Plugging completed April 3 1973
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	224	None
				7	3846	1748

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character, of same and depth placed, from _____ feet to _____ feet for each plug set.

March 26, 1973 Plugged off bottom. Dumped sand to 3700'. Mixed and dumped 7 sx of cement.
April 3, 1973 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 10 3/4" surface casing; 3 sx of hulls, 20 sx of gel and 125 sx of cement.

4-23-73


RECEIVED
STATE CORPORATION COMMISSION
APR 23 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) J. A. Gilliland
Office Manager

SUBSCRIBED AND SWORN to before me this 10th. day of April, 1973.
My commission expires August 26, 1973
Ariene L. Sloop Notary Public.



DRILLERS LOG

COMPANY: Natural Gas and Oil Corporation and Oklahoma Exploration Company

FARM: Enlow #2, NE SE NW Sec. 9-24S-16W, Edwards County, Kansas

CONTRACTOR: Drilling Department of Natural Gas & Oil Corp

COMMENCED: November 1, 1953 - Rotary
November 19, 1953 - Cardwell

COMPLETED: November 17, 1953 - Rotary
November 23, 1953 - Cardwell

ELEVATION: 2076 RB.

0	to	100	Shale and sand
100	to	225	Shale and shells
225	to	690	Shale-sand-red bed
690	to	1017	Red bed and shale
1017	to	1042	Anhydrite
1042	to	1450	Shale and shells
1450	to	1600	Salt-shale and shells
1600	to	1900	Lime and shale
1900	to	2010	Lime
2010	to	2210	Lime and shale
2210	to	2440	Lime
2440	to	3330	Lime and shale
3330	to	3385	Lime
3385	to	3691	Lime and shale
3691	to	3695	Brown lime
3695	to	3699	Lime and shale
3699	to	3865	Lime
3865	to	4109	Lime and shale
4109	to	4135	Lime and chert
4135	to	4137	Lime
4137	to	4158	Lime and shale
4158	to	4216	Lime and chert
4216	to	4252	Lime
4252	to	4265	Granite Wash.

4-23-73
RECEIVED
STATE CORPORATION COMMISSION
APR 23 1973
CONSERVATION DIVISION
Wichita, Kansas

Set 224 ft of 10 3/4" 32# surface. Cemented with 250 sacks cement and 4 sacks calcium chloride.

Set 7" 20# casing at 3846. Cemented with 200 sacks cement.

TOPS:	Anhydrite	1017	Mississippi	4105
	Brown Lime	3691	Viola	4157
	Lansing	3700	Pre Cambr.	4252
	Base K. C.	3957		

DRILL STEM TESTS:

- #1 3701-11, open 1 hr, shut in 20 min, gas to surface in 42 min, recovered 10' heavily oil cut mud, 180' froggy oil & gas cut mud, FFP 95#, BHP 12230#.
- #2-3716-40, open 1 hr, gas to surf in 12 min, recovered 2280' free oil, 20' heavily mud cut oil, IFP 150#, FFP 500#, BHP 1170#.
- #3-3787-3830, open 1 hr, shut in 20 min, good blow, recovered 625' salt water, IFP 50#, FFP 390#, BHP 1130#.
- #4-3878-3915, open 1 hr, shut in 20 min, fair blow thruout, recovered 200' salt water, IFP 60#, FFP 150#, BHP 1290#.
- #5-4071-4109, open 1 hr, shut in 20 min, fair blow, rec 30' mud, BHP 200#.
- #6-4111-4137, open 1 hr, shut in 20 min, strong blow, rec 30' mud, BHP 400#.
- #7-4143-83, open 1 hr, shut in 20 min, gas to surf in 50 min, recovered 35' gas cut mud, BHP 410#.

Ran Schlumberger, also Lane-Wells

Perforated 48 Kone shots 3728-36, no fillup, swabbed 2 BO for 4 hours natural, 11/22/53 ran tubing to 3764, acidized with 200 gallon mud acid and 500 gallons Dowell X. Pulled swab and well started flowing, flowed 12 1/2 BO on 1/2" choke on 3 hr test. no water. Shut in for tank room.

11/25/53 Filed 25 BOPG Temporary Affidavit as of 11/22/53

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the Enlow #2, NE SE NW Section 9-24S-16W, Edwards County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.

Harold A. Burt
Harold A. Burt, Regional Manager

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 27th day of November, 1953.

Esther Unsell
Esther Unsell, Notary Public

My Commission expires May 25, 1957.

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1973
CONSERVATION DIVISION
Wichita, Kansas