

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-21,227-0000

LEASE NAME Coppoc-Rudd

WELL NUMBER #3-9

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 24S RGE. 16W (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 3/8/89

Plugging Completed 3/21/89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl

c/o Art Merrick

ADDRESS P.O. Box 158

Belpre, KS 67519

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
				8 5/8	309	none
				4 1/2	4335	2241

Describe in detail the manner in which the well was plugged, indicating where the cement fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom was already plugged with 25 sacks 60/40 poz 6% gel, top of plug @3798', shot @2465', 2380', 2296', 2241', pulled 54 joints, plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls, 8 5/8" plug 125 sacks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address * P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 89

Jane Hoover

Notary Public

My Commission Expires:



STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- COPPOC-RUDD #3-9
 Located: NW SW SE, Section 9-24S-16W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 18, 1984

COMPLETED: November 24, 1984

TOTAL DEPTH: 4340'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 311 Surface Soil, sand and clay	Ran 7 joints new 8 5/8" OD casing. 296.40' pipe set at 309' K. B. Cemented with 210 sacks Common, 2% gel and 3% cc. Plug down at 10:15 PM, 11-18-84, by Howco.
311 - 1400 Shale	
1400 - 1900 Shale and Lime Stringers	
1900 - 4340 Lime and Shale	Ran 106 joints new 4 1/2" OD casing. 4325.04' pipe set at 4335' K.B. Cemented with 100 sacks Howco Lite and 125 sacks 50/50 Pozmix plus F. G. Holl regular additives, followed with regular flush. Plug down at 4:00 PM, 11-24-84, by Howco.

RECEIVED
 STATE CORPORATION COMMISSION

FEB 23 1989 2-23-89

CONSERVATION DIVISION
 Wichita, Kansas

Deviation Surveys: 1 3/4° at 2042'
 2° at 4230'