

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. X Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR F. G. HOLL
 ADDRESS 6427 East Kellogg
Wichita, Kansas 67207
 **CONTACT PERSON Flwyn H. Nagel
 PHONE (316) 684-8481
 PURCHASER Clear Creek, Inc.
 ADDRESS 818 Century Plaza Building
Wichita, Kansas 67202
 DRILLING Sterling Drilling Company
 CONTRACTOR
 ADDRESS P. O. Box 129
Sterling, Kansas 67579

API NO. 15-047-20.978-6006
 COUNTY Edwards
 FIELD Enlow-massey
 PROD. FORMATION Kinderhook
 LEASE HAWLEY
 WELL NO. 6-7
 WELL LOCATION NW SW NW
330 Ft. from West Line and
990 Ft. from South Line of
 the NW/4 SEC.7 TWP. 24S RGE 16W

PLUGGING N.A.
 CONTRACTOR
 ADDRESS
 TOTAL DEPTH 4375 PBT
 SPUD DATE 12/14/81 DATE COMPLETED 12/20/81
 ELEV: GR 2085 DF 2091 KB 2094

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 09 1982
 8-9-82
 CONSERVATION DIVISION
 Wichita, Kansas

WELL PLAT
 KCC
 KCS
 MISC
 (Office Use)

DRILLED WITH ~~CABLE~~ (ROTARY) ~~TOOLS~~ (New) / ~~Used~~ casing.
 CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		8 5/8	24	253	60/40 Pozmix	210	3% cc
PRODUCTION		4 1/2	10.5	4370	Lite	100	
					50/50 Pozmix	125	Regular

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Golden Jets	4320-24
			4	Golden Jets	4284-88

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15% MCA	4320-24
500 gal. 15% MCA 800 bbl SW frac with 20-40 and 10-20 sand 20 Sealer balls	4284-88

Date of first production February 16, 1982 Producing method (flowing, pumping, gas lift, etc.) Pumping Gravity
 RATE OF PRODUCTION PER 24 HOURS Oil 10 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio 0 CFPD
 Disposition of gas (vented, used on lease or sold) Perforations 4320-24; 4284-88

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum N.A. Depth

Estimated height of cement behind Surface Pipe Cement Circulated.

DV USED? NO

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Surface Soil and Sand	0	110		
Shale	110	256		
Shale and Sand	256	650		
Shale	650	1102	Heebner	3685
Anhydrite	1102	1118	Brown Lime	3813
Shale	1118	1290	Lansing KC	3821
Lime and Shale	1290	4270	Base KC	4103
Lime and Chert	4270	4304	Cherokee Sh	4225
Lime and Shale	4304	4375	Cherokee Sd	
			Conglomerate	4260
			Conglomerate	
			Chert	
			Mississippi	4277
			Kinderhook	
			Shale	4299
			Kinderhook	
			Sand	431-
			Viola	4350
			Simpson Sh	
			Simpson Ss	
			Arbuckle	
			RTD	4375
			Elog TD	4375
<p>DST #1 4245-4303 Tool opened with strong blow; gas to surface in 23', gauged 28,000 DFG/D; 26,100 CFG/D at end of test. Recovered 3600' clean, gassy oil. Pressures; IFP 644 30" ISIP 804 30' FFP 793 60" FSIP 804 30"</p>				

AFFIDAVIT

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

Elwyn H. Nagel OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Geologist (FOR)(OF) F. G. HOLL

OPERATOR OF THE HAWLEY LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 6-7 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 29th DAY OF January, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 6th DAY OF August 19 82

(s) Elwyn H. Nagel
 Elwyn H. Nagel Geologist

Mary D. Slagle
 NOTARY PUBLIC

MY COMMISSION EXPIRES

