

15-151-19103-00.02

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued March 23, 1967.RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1967
3-30-67
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name High Plains Production CompanyComplete Address: 304 Insurance Bldg., Wichita, KansasLease Name Shriver Well No. # 1Location C E/2 SW SE Sec. 14 Twp. 29 Rge. 14 (E) (W)County Pratt Total Depth 4544'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.Address: Stafford, Kansas License No. 490Operation Completed: Hour 11:30AM Day 27th Month March Year 1967

The Above well was plugged as follows:

785' of 8 5/8" surface pipe, cement circulated. 4537' of 4 1/2" long string,
cemented with 225 sacks. This is an open hole. 4 1/2" long string had collapsed
at 2150', pipe was sanded to 2100', and cemented with 3 sacks, through the
dump bailer. 2037' of 4 1/2" long string was recovered from the hole. Fluid
in the hole was bailed down to 400', rock bridge and bridge plug from 400'
to 380', and hole was filled with 6 yards of ready-mix cement from 380' to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/30/67
INV. NO. 4995-WSigned: Archie Elving
Well Plugging Supervisor