

9

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 1 1963
10-1-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Wilco Oil Inc.

Complete Address: Box 13528, Phoenix, Arizona

Lease Name Klein Well No. # 1

Location SW NE SE Sec. 2 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 3805

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Co.

Address: 204 E. Sixth St., Ellinwood, Kansas License No. 396

Operation Completed: Hour 12:00PM Day 29th Month Sept. Year 1963

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cemented to top. 3805' of 5 1/2" long string,
cemented with 125 sacks. Top perferation 3650'. Bottom hole plug was
pushed to 3600', with rock bridge, cemented with 5 sacks. Hole was bailed
to 280', plug was set at 280', bridged with 10' of rock, cemented with
30 sacks. Hole was filled with mud to 40', 10' rock bridge, cemented
with 10 sacks to base cellar.

2596' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

NOTICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10-1-63

INV. NO. 7822-W