

Form CP-3
Rev. 6-26-62

W
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1963
11-4-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Wilco Oil Inc.

Complete Address: Box 13528, Phoenix, Arizona

Lease Name Klein Well No. # 2

Location SE NE SE Sec. 2 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 3963

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Co.

Address: 204 East Sixth, Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30AM Day 2nd Month Nov. Year 1963

The Above well was plugged as follows:

326' of 8 5/8" surface pipe, cemented to top. 3961' of 5 1/2" long string,
cemented with 125 sacks. Top perforation 3652'. Plug was pushed to 3600',
bridged with rock and cemented with 5 sacks. Pipe was shot off at 3040',
and gas erupted, 200 sacks of cement was pumped into long string, through
5 1/2" swage, to kill gas. Fluid level was up in hole. Plug was pushed to
275', 10' rock bridge, 5 sacks of cement was mixed in barrel, and put on
plug through dump bailer, and let set over night. Next morning hole bail-
ed down, and 20 sacks cement was added to plug. Hole was filled with mud to
40', 10' rock bridge, cemented with 10 sacks to base cellar.

I hereby certify that the above well was plugged as herein stated.
2323' of 5 1/2" long string was recovered from the hole.

INVOICED

Signed: Archie Ewing
Well Plugging Supervisor

DATE 11/4/63

INV. NO. 8009-W