

KANSAS

STATE CORPORATION COMMISSION
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

AUG 10 1976
8-10-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name F G Holl & Sterling Drlg Co

Complete Address 6427 E Kellogg Wichita, KS

Lease Name Hawley Well No. 1

Location C NE Sec. 7 Twp. 24 Rge. 16 (E) (W)^W

County Edwards Total Depth 4360

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 3:00 PM Day 7 Month 8 Year 1976

The above well was plugged as follows:

275 ft 8 5/8 surface cemented with 275 sacks. 4359 ft 4 1/2 long string
cemented with 150 sacks. Top perf. 4252 ft. Sand to 4200 ft, 4
sacks cement with bailer. Pulled 3418 ft 4 1/2. Pump 2 sacks hulls,
10 sacks gel, 100 sacks cement to surface.
Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated?

INVOICED

DATE 8/10/76

INV. NO. 3607-W

Signed: [Signature]
Well Plugging Supervisor