

2

KANSAS

Form CR-3 ED
STATE CORPORATION COMMISSION
Rev. 6-24-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

AUG - 6 1979
8-6-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185 - 20,451-000 (of this well)

Operator's Full Name Vincent Oil Corp.

Complete Address 230 O.W. Garvey Bldg., Wichita, Ks. 67202

Lease Name Cummins Well No. 1

Location E/2 E/2 SW Sec. 33 Twp. 24s Rge. 15 (E) (W)

County Stafford Total Depth 4289

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 2:30 Pm. Day 2 Month 8 Year 1979

The above well was plugged as follows:

317' 8 5/8" casing w/225 sax cement. 4 1/2" casing set at 4288' w/160
sax cement. Plug back to 4256'-Top pref. at 4184'-4194'-Sand back to
4150'-Top sand w/4 sax mixed cement w/ dump bailer-Pull 1925' 4 1/2"
casing-Allied mixed & pumped 8 sax hulls-25 sax gel-Release plug-
mixed & pumped 200 sax 50/50 posmix cement w/4% gel & .3% cc to top
of casing. Shut in w/500# pressure. Note: This well was plugged as a
gas well. It was being used for a disposal well. They had a 3" plastic
line under ground tied to the 8 5/8" casing well head & was disposing
salt water down the 8 5/8" casing between the 8 5/8" & the 4 1/2" casing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 8-7-79

INV. NO. 0144-W