

*40*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 20 1963  
8-20-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kansas

Lease Name Eichenberger "A" Well No. # 1

Location NE NE NE Sec. 31 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4335

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Aylward Drilling Co.

Address: 909 1st National Bank Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 6:00PM Day 17th Month August Year 1963

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cemented with 200 sacks. Fluid level was  
up in the hole. Plug and 1/4 sack hulls was pushed to 260', cemented  
through drill pipe with 20 sacks cement. Hole was filled with mud  
to 40', 2nd cementing plug, 1/4 sack hulls, cemented with 10 sacks to  
base cellar. Rat hole bridged and cemented with 2 sacks,

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/20/63  
INV. NO. 9619-u